Fig. 133 Building 138 Emergency Washroom No 7

Fig. 134 Building 138 Emergency Washroom No 7

4.22 Building 139 ARP Shelter (adjacent to building 138)

This building follows the same configuration as those elsewhere at the Valley, with entrance doors in the south-west and north-east corners. The building is constructed in English bond with a cast in-situ reinforced concrete roof slab.

The reinforced concrete roof slab appears to have never had any bituminous covering and exhibits a certain amount of deterioration particularly along the east side, where the reinforcement is exposed in some areas. The brickwork to the east elevation is also suffering with a number of spalled faces. Significant to this ARP Shelter is the retention of the frame for the entrance curtain with a small amount of the original fabric. The original entrance door and ironmongery to the south-eastern corner also remain in-situ, and in good condition. This is the only one remaining on site, and is therefore quite significant. Internally the lack of bituminous covering on the roof means that the underside of the roof slab is very wet. Consequently the internal space the floor is quite damp and covered in debris.

4.23 Building 146 Wood Waste and Box Room 28

This building forms the northern-most end of a series of buildings linked to the railway platform extending from the south-eastern corner of building 146 to the south linking up with building 149. Building 146 is a single storey brick structure, constructed in stretcher bond with a cavity, surmounted by reinforced concrete roof slab. The building is entered by a projecting porch to the south adjoining the railway platform.

4.23.1 Roofs

The roof to the main building has a replacement bituminous roofing felt much of which is now missing around the perimeter of the roof slab. The slab itself has not started to decay to the extent of some of the others, however, the failure in the roof covering is significant and will be allowing water penetration.

There is horizontal and diagonal cracking a couple of courses below the reinforced concrete roof slab, particularly evident along the south elevation, and along the projecting porch on the south elevation, and particularly on the eastern corner. The roof slab to the porch has also been covered in a replacement felt, this is also failed and cracking.

It was possible at the time of survey to view the top surface of the porch roof, this is covered in reflective chippings also suggesting that this is a replacement covering. The flashing between the porch and the main building was originally lead, however this has been removed allowing water ingress between the main building and the porch.

4.23.2 Walls

The south elevation is plain brick work with a section concealed by the projecting railways platform in the south east corner. There is cracking to the brickwork associated with the distortion in the roof slab at high level, otherwise the brick work is generally in reasonable condition. The east elevation is plain brick with a ventilator approximately one third of the way along from the south, generally this is in reasonable condition and there is retention of the camouflage paint finish, there is however some limited horizontal and diagonal cracking at high level adjoining the roof slab. The west elevation mirrors the east in is in similar condition.

The north elevation is plain brickwork with two ventilators some two metres off the ground, both of which are missing their original louvred vents. There are significantly more spalled bricks on this elevation and there is also evidence of a small enclosure or adjoining structure at low level as there are modifications in the brick work and a small concrete plinth adjacent.

4.23.3 Interior

The building is accessed through the porch on the south elevation. The interior of the porch is in good order, no evidence of significant water ingress and much of the original cementitious plaster and the paint finish remains in-situ. In the main space, to the underside of the roof slab, there is evidence of water ingress, however the slab itself is generally in reasonable condition at the time of survey. To the walls, at high-level in each corner, there is significant cracking at high level as evidenced in each of the buildings of this type. However the walls retain their original cementitious plaster finish, the cream paint and the shift markings. The floor to this building is synthaprufe extending through from the walkway outside and turned up the walls in a coved skirting. This is largely covered in debris but appears to be in reasonable condition. There is evidence of the modification at low level on the north wall internally with a section of modern brick work.

4.23.4 Railway Platform

Extending to the south of the building 146 is the railway platform. This comprises of a brick substructure with a reinforced concrete slab forming the platform top. The whole is then covered in the synthaprufe/anti-spark coating. The slab projects to form a cantilever to the platform edge to the east. Much of the brick structure is badly cracked and delaminating and the synthaprufe is missing along the western edge, causing the reinforced concrete underneath to deteriorate. To the southern end, adjoining building 149 there is a series of four steps also finished in synthaprufe. To the west of the railway platform there is a section of wall and a pier. This section of wall is in quite poor condition with much of the brick coating having failed and many brick having delaminated faces.

Fig. 135 Building 146 Wood Waste and Box Room 28 and adjacent railway platform

Fig. 136 Building 146 Wood Waste and Box Room 28

Fig. 137 Building 146 Wood Waste and Box Room 28

Fig. 138 Building 146 Wood Waste and Box Room 28

4.24 Building 148 Smoke Box Store

This building is a simple square brick structure, of the same configuration as building 136, with a reinforced concrete roof accessed by a porch projecting towards the south. The building is constructed in stretcher bond with a cavity. The reinforced concrete roof retains much of its roof covering, the finish appears to have been replaced with a felt covering. This is however missing to the down stands particularly to the south and east elevations. The brickwork to the building is generally in reasonable condition, minor cracking to each corner at high level adjoining the roof slab. The north elevation has a number of spalled bricks. To the east and west elevations there are two ventilators to each wall. The zinc louvred vents have been removed.

Internally the porch retains much of its original decorative finish however; there is evidence that the flashing has been removed between the porch and the main building allowing water ingress.

To the main space, the underside of the roof slab is quite wet and there is a crack adjoining the central roof vent. Algal staining to the underside of the roof suggests some significant water ingress. The main space is rendered in the cementitious render seen elsewhere and there is some evidence of the original cream wartime paint finish. However, this is failing because the structure is quite wet. The floor is covered in debris, leaf matter and soil. It was not possible to ascertain the original floor covering in the main space, however the synthaprufe from the walk ways extends to the porch area.

4.25 Building 149 M.L. Case and Fuse Box Store 25

This is a single storey brick building constructed in stretcher bond with a cavity. The building is accessed through projecting porch on the north elevation and as referenced, adjoins the railway platform in the north eastern corner. However, this is surmounted by a reinforced concrete roof slab.

4.25.1 Roofs

The roof is a reinforced concrete roof slab of the pre-cast type with down-stand beams. It is missing much of its covering around the perimeter of the roof particularly on the east elevation where there is very little left on the face of the reinforced concrete slab. To each of the four corners of the building there is an area of localized reconstruction to the brickwork below the slab, suggesting that the cracking has been a problem for some considerable time. Projecting from the roof there are four ventilators with cowls, two on the east and two on the western side of the building. The roof slab to the projecting porch is again covered in the replacement roofing felt with chippings. This is in better condition.

4.25.2 Walls

The brickwork to the south elevation, either side of the projecting porch, is generally in good condition, with very few spalled brick faces. There is a chase into the brick work where it adjoins the railway platform allowing the synthaprufe to be turned up to form a flashing. The synthaprufe has since shrunk and cracked away allowing water ingress in this area. At high-level there are two ventilators both of which are missing their original louvred vents. At high-level to each corner of the building there is an area of reconstruction in more modern brick work. Adjoining the projecting porch where there was o

riginally a down pipe, now missing and there is a tree growing out of this area in very close proximity to the building, which needs to be removed. The west elevation is plain brickwork with four ventilators at high level and retains significant proportion of its original camouflage paint. There is a significant diagonal crack some three metres in from the north end running down through the wall.

At the south end of the building there is a timber feature attached to the wall, it is not clear if this is associated with the wild life habitat or if it covers up some other feature. Around this there is also some localized reconstruction at high level. The south elevation of the building is also plain brick with some limited localized reconstruction at high level to each corner but once again the brickwork is largely in good order. There are two vents at high level both missing their original zinc louvred ventilators and another timber feature secured to the wall towards the eastern end of the elevation. The east elevation mirrors the west; however, there are areas of delaminating brick. The water from the roof is discharging down the wall face, evidenced by algal growth and staining on this elevation, at high level there are four holes which would have housed louvered vents which are all missing and to each corner there are two areas of reconstruction in modern brick work.

4.25.3 Interiors

The building is accessed from the porch at the northern end. The porch is generally in reasonable condition and the underside of the roof slab is largely dry. Most of the cementitious render remains in-situ with its original grey paint finish and the delineation around the position for the fire extinguishers. The synthaprufe walkway extends to the porch up to a timber threshold beyond this the floor becomes linoleum, which is badly cracked and failing.

In the main space the underside of the roof slab is generally in reasonable order with limited signs of water ingress, except for an area adjoining the pier in the centre of the east wall where the water ingress is quite severe resulting to failure to the plaster and the paint finishes, and cracking to the underside of the roof slab.

The walls are plastered and finished in the cementitious render and are finished in the early cream paint with the shift markings to the north and south walls. There is evidence of the longitudinal cracking to each corner at high level. However, this is less pronounced than in other buildings. The floor as previously mentioned is linoleum but this is largely obscured by debris and other detritus.

Beyond building 149 there is a section of free standing wall, surmounted by a brick coping. To this feature, there are significant number of spalled and failing bricks due to the inadequacy of the brick coating and the consequential saturation of the wall. Adjoining the wall there is a slab and a further area of raised ground to the south of the wall.

The space to the northern end of the building retains its original toilet cubicles, there is further deterioration to the underside of the reinforced concrete floor structure in this area and there is also cracking to the floor slab, particularly adjacent to the entrance doors.

Fig. 139 Building 149 ML Case and Fuse Box Store

Fig. 140 Building 149 ML Case and Fuse Box Store

Fig. 141 Railway Platform

Fig. 142 Railway Platform

Appendix A

Listed Building Descriptions

cadw

Llywodraeth Cymru
Welsh Assembly Government

Ancient Monuments and Archaeological Areas Act 1979

Scheduling Maplet for SAM No. FL210(FLT)

Ministry of Supply Valley Site



This is the Plan referred to in the Scheduling entry dated

10 September 2008

Signed by Matthew Coward under authority of the Minister for Heritage, one of the Welsh Ministers

Matthew Coward

File Reference: **A-CAM-01-01-7980**

National Grid Reference: **SJ 2052 6609**

Scale: **1:5,000**

'This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationary Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.' Licence Number GD272221

'Atgynhyrchir y map hwn o Ddeunydd yr Arolwg Ordnans gyda chaniatâd Arolwg Ordnans ar ran Rheolwr Llyfrfa Ei Mawrhydi © Hawlfraint y Goron. Mae atgynhyrchu heb ganiatâd yn torri hawlfraint y Goron a gall hyn arwain at erlyniad neu achos sifil.' Rhif Trwydded GD272221

Authority	Flintshire	Record No	87560
		DateListed	10/09/2008
Community	Cilcain		
Locality	Rhydymwyn	Grid Ref	320685 366380
		Grade	II

Name **Pyro Building P4 (Carillion Building 59) at Rhydymwyn Valley Site**

Street No, Name **Nant Alyn Road**

Location

On very large site to the SW of the A 541 at Rhydymwyn. This building is the southernmost of the large Pyro Plant buildings, about 500 metres S of Nant Alyn Road.

History

For full history and analysis of the site and an explanation of the chemical processes see the Birmingham Archaeology report cited below.
The Ministry of Supply Valley Works, Rhydymwyn was built to produce mustard gas for military purposes, and to assemble, charge, and store chemical weapons. Important research took place here in the early development of atomic weapons.
In response to the use by Germany of poison gas in the First World War, Britain developed chemical warfare capacity. As war threatened again in the later 1930s, the Government, in association with industry, developed a series of new plants. Work at MS Valley began in 1939, and the site became operational in 1942. It continued to produce mustard gas until the end of the War. The works were run by ICI on behalf of the Ministry of Supply. After the War, stocks were gradually decommissioned.
The works was developed on a large site with distinct zones for production of mustard products, filling of shells and bombs, arming the weapons, and storage in tunnels in the hillside, as well as laboratories and administration areas. Three plants were built to produce the Pyro variant of mustard gas and and two plants to produce the Runcol variant. Although two of the Pyro plants were commissioned they never went into full production. The third Pyro building was used for research in connection with the enrichment of uranium.
This building, P4 (as well as P5 and P6) was intended to house plant for the production of Pyro mustard, a less stable variant. However, as the threat of invasion receded, none of the buildings was used for production. P5 was used to refine Pyro mustard produced at other factories. Building P4 was a fully-operational back-up plant.

Exterior

A very large building of reinforced concrete frame construction with infill of red brickwork laid in English bond. Seven bays to long (east and west) elevations; on lower level of W elevation each bay formerly had 2 openings (ie 14 in all) now blocked.
The central section of 5 bays has segmental concrete vault over each bay. At each end a bay with flat roof. The N & S elevations have six bays externally. Square concrete tower to N over second bay from W. Much alteration and blocking of original openings. In S elevations, later insertions of two large-vehicle entrances.

Interior

The interior is articulated by reinforced concrete posts; some circular openings to roof. Overhead rails for lifting gear. Building is divided longitudinally into 2 areas; to W the toxic area of 3 bays, and to E the non-toxic area of 2 wider bays.
At N end of non-toxic side, small single-storey divisions for two transformers and switch room. Remains of switchgear and fire-fighting equipment.

Listed

As part of a group of buildings, which along with the Scheduled buildings in the Danger Area and the Scheduled storage tunnels [FL210(FLT)] illustrate the industrial processes behind chemical weapons production to an extent unique in the UK. Group value with the other listed buildings on the site.

Reference

Birmingham Archaeology, The Valley Site, Rhydymwyn, Flintshire. Historic Environment Plan, Vols 1-3, 2007.

Authority	Flintshire	Record No	87561
		DateListed	10/09/2008
Community	Cilcain		
Locality	Rhydymwyn	Grid Ref	320656 366555
		Grade	II

Name **Pyro Building P5 (Carillion Building 50) at Rhydymwyn Valley Site**

Street No, Name **Nant Alyn Road**

Location

On very large site to the SW of the A 541 at Rhydymwyn. This building is about 100m W of the old railway, and about 300 metres S of Nant Alyn Road.

History

For full history and analysis of the site and an explanation of the chemical processes see the Birmingham Archaeology report cited below.
The Ministry of Supply Valley Works, Rhydymwyn was built to produce mustard gas for military purposes, and to assemble, charge, and store chemical weapons. Important research took place here in the early development of atomic weapons.
In response to the use by Germany of poison gas in the First World War, Britain developed chemical warfare capacity. As war threatened again in the later 1930s, the Government, in association with industry, developed a series of new plants. Work at MS Valley began in 1939, and the site became operational in 1942. It continued to produce mustard gas until the end of the War. The works were run by ICI on behalf of the Ministry of Supply.
After the War, stocks were gradually decommissioned.
The works was developed on a large site with distinct zones for production of mustard products, filling of shells and bombs, arming the weapons, and storage in tunnels in the hillside, as well as laboratories and administration areas.
Three plants were built to produce the Pyro variant of mustard gas and and two plants to produce the Runcol variant. Although two of the Pyro plants were commissioned they never went into full production. The third Pyro building was used for research in connection with the enrichment of uranium.
This building, P5 (as well as P4 and P6) was intended to house plant for the production of Pyro mustard, a less stable variant. However, as the threat of invasion receded, none of the buildings was used for production. P5 was used to refine Pyro mustard produced at other factories.

Exterior

A very large building of reinforced concrete frame construction with infill of red brickwork laid in English bond.
Seven bays to long (east and west) elevations; on lower level of W elevation each bay formerly had 2 openings (ie 14 in all) now blocked.
The central section of 5 bays has segmental concrete vault over each bay. At each end a bay with flat roof. The N & S elevations have six bays externally. Square concrete tower to N over second bay from W. Much alteration and blocking of original openings. In S elevations, later insertions of two large vehicle entrances.

Interior

The interior is articulated by reinforced concrete posts; some circular openings to roof. Overhead rails for lifting gear. Building is divided longitudinally into 2 areas; to W the toxic area of 3 bays, and to E the non-toxic area of 2 wider bays.
At N end of non-toxic side, small single-storey divisions for two transformers and switch room.

Listed

As part of a group of buildings, which along with the Scheduled buildings in the Danger Area and the Scheduled storage tunnels [FL210(FLT)] illustrate the industrial processes behind chemical weapons production to an extent

unique in the UK. Group value with the other listed buildings on the site.

Reference

Birmingham Archaeology, The Valley Site, Rhydymwyn, Flintshire. Historic Environment Plan, Vols 1-3, 2007.

Authority	Flintshire	Record No	87562
		DateListed	10/09/2008
Community	Cilcain		
Locality	Rhydymwyn	Grid Ref	320508 366538
		Grade	II

Name **Pyro Building P6 (Carillion Building 45) at Rhydymwyn Valley Site**

Street No, Name **Nant Alyn Road**

Location

On very large site to the SW of the A 541 at Rhydymwyn. This building is the westernmost of the large Pyro Plant buildings, about 300 metres S of Nant Alyn Road.

History

For full history and analysis of the site and an explanation of the chemical processes see the Birmingham Archaeology report cited below.
The Ministry of Supply Valley Works, Rhydymwyn was built to produce mustard gas for military purposes, and to assemble, charge, and store chemical weapons. Important research took place here in the early development of atomic weapons.
In response to the use by Germany of poison gas in the First World War, Britain developed chemical warfare capacity. As war threatened again in the later 1930s, the Government, in association with industry, developed a series of new plants. Work at MS Valley began in 1939, and the site became operational in 1942. It continued to produce mustard gas until the end of the War. The works were run by ICI on behalf of the Ministry of Supply. After the War, stocks were gradually decommissioned.
The works was developed on a large site with distinct zones for production of mustard products, filling of shells and bombs, arming the weapons, and storage in tunnels in the hillside, as well as laboratories and administration areas. Three plants were built to produce the Pyro variant of mustard gas and and two plants to produce the Runcol variant. Although two of the Pyro plants were commissioned they never went into full production. The third Pyro building was used for research in connection with the enrichment of uranium.
This building, P6 (as well as P4 and P5) was intended to house plant for the production of Pyro mustard, a less stable variant. However, as the threat of invasion receded, none of the buildings was used for full production. At P6 plant was not installed. From 1941-43, and again in 1946, it was used for experiments in the enrichment of uranium by gaseous diffusion in connection with the development of the atomic bomb. The project was code named "Tube Alloys". In 1943, following an agreement by Britain and the USA to concentrate research in America, development was stopped on this site, and most of the scientists from the British project were transferred to the USA. The building was adapted with the insertion of offices and laboratories in the E side.

Exterior

A very large building of reinforced concrete frame construction with infill of red brickwork laid in English bond. Similar to Pyro buildings P4 and P5, but reversed by 180 degrees. Seven bays to long (east and west) elevations; on lower level of E elevation each bay formerly had 2 openings (ie 14 in all) now blocked.
The central section of 5 bays has segmental concrete vault over each bay. At each end a bay with flat roof. Six bays externally to short elevations Square concrete tower to S over second bay from E. Much alteration and blocking of original openings.

Interior

The interior is articulated by reinforced concrete posts; some circular openings to roof. Overhead rails for lifting gear. Building is divided longitudinally into 2 areas; to W an area of 2 wide bays, and to E an area of 3 more narrow bays; this area has been subdivided to make laboratory/ office areas. Marks in floor from bases of gaseous diffusion machinery. At S end of W area, small single-storey division probably for switch room. At upper level against N and S walls, steam air heating ducts.

Listed

As part of a group of buildings, which along with the Scheduled buildings in the Danger Area and the Scheduled storage tunnels [FL210(FLT)] illustrate the industrial processes behind chemical weapons production to an extent unique in the UK. This building has additional historic interest as the site of the experiments connected with the enrichment of uranium for weapons purposes. Group value with the other listed buildings on the site.

Reference

Birmingham Archaeology, The Valley Site, Rhydymwyn, Flintshire. Historic Environment Plan, Vols 1-3, 2007.

Authority	Flintshire	Record No	87563
		DateListed	10/09/2008
Community	Cilcain		
Locality	Rhydymwyn	Grid Ref	320623 366327
		Grade	II

Name **Runcol Building R3 (Carillion Building 65) at Rhydymwyn Valley Site**

Street No, Name **Nant Alyn Road**

Location

On very large site to the SW of the A 541 at Rhydymwyn. This building is to the SW of the large Pyro Plant building P4, and about 650 metres S of Nant Alyn Road.

History

For full history and analysis of the site and an explanation of the chemical processes see the Birmingham Archaeology report cited below.
The Ministry of Supply Valley Works, Rhydymwyn was built to produce mustard gas for military purposes, and to assemble, charge, and store chemical weapons. Important research took place here in the early development of atomic weapons.
In response to the use by Germany of poison gas in the First World War, Britain developed chemical warfare capacity. As war threatened again in the later 1930s, the Government, in association with industry, developed a series of new plants. Work at MS Valley began in 1939, and the site became operational in 1942. It continued to produce mustard gas until the end of the War. The works were run by ICI on behalf of the Ministry of Supply. After the War, stocks were gradually decommissioned.
The works was developed on a large site with distinct zones for production of mustard products, filling of shells and bombs, arming the weapons, and storage in tunnels in the hillside, as well as laboratories and administration areas. Three plants were built to produce the Pyro variant of mustard gas and and two plants to produce the Runcol variant. Although two of the Pyro plants were commissioned they never went into full production. The third Pyro building was used for research in connection with the enrichment of uranium.
This building, R3, was built for the production of the Runcol variant of mustard
Another building, R4 to the same design formerly stood further north. Both buildings produced large quantites of Runcol.

Exterior

Rectangular building with concrete frame with infill panels of red brickwork laid in English bond. Flat roof. Facing roadway, six bays; the first and fourth (from SE) are broader. At SE end, a doorway (narrowed) and at upper level a window with small-pane glazing. SW elevation has 2 low rectangular blocks which were pump room and syrup room; stairs between. NW end has at upper level a window (reduced in size).

Interior

Divided into 2 areas. Longer SE area (reaction section) has raised platform on SW side which formerly bore production equipment. At NW end, doorway through to acid generator section. Overhead crane and some internal details remain.

Listed

As part of a group of buildings which along with the Scheduled buildings in the Danger Area and the Scheduled storage tunnels [FL210(FLT)] illustrate the industrial processes behind chemical weapons production to an extent unique in the UK. Group value with the other listed buildings on the site.

Reference

Birmingham Archaeology, The Valley Site, Rhydymwyn, Flintshire. Historic Environment Plan, Vols 1-3, 2007.

Dated:- 10 September 2008

Signed by Laurence Burr under authority of the Minister for Heritage, one of the Welsh Ministers

L H BURR
Head of Designations Section
Cadw
Welsh Assembly Government

Listed Building

Pyro Building P4 -6 (Carillion Buildings 59,50,45)
Runcol Building R3 (Carillion Building 65)
Rhydymwyn Valley Site

Plas Carew, Unit 5/7 Cefn Coed
Parc Nantgarw,
Cardiff CF15 7QQ
Tel: 01443 336000
Fax: 01443 336001
Email: cadw@wales.gsi.gov.uk
Web: www.cadw.wales.gov.uk

Plas Carew, Uned 5/7 Cefn Coed
Parc Nantgarw,
Caerdydd CF15 7QQ
Ffôn: 01443 336000
Ffacs: 01443 336001
Ebost: cadw@wales.gsi.gov.uk
Gwefan: www.cadw.wales.gov.uk

BUILDINGS OF SPECIAL ARCHITECTURAL OR HISTORIC INTEREST



Sheet.	Authority : FLINTSHIRE	File No :	A-CL 117/06/025
		Ordnance Survey Grid Reference :	see above
Scale 1:2500	Community : CILCAIN	Ordnance Survey Sheets :	SJ 2066

+Cadw

Llywodraeth Cynulliad Cymru
Welsh Assembly Government

Cadw yw cyfarwyddiaeth amgylchedd hanesyddol Llywodraeth Cynulliad Cymru
Cadw is the historic environment Directorate of the Welsh Assembly Government

Seiliwyd y map hwn ar fap Arolwg Ordnans gan Gynulliad Cenedlaethol Cymru gyda chaniatâd yr Arolwg Ordnans ar ran Rheolwr Llyfrfa Ei Mawrhydi, © Hawlfraint y Goron. Caniatâd pellach sydd ei angen cyn atgynhyrchu neu gwerthu yn unrhyw fformat a gallai arwain at erlyn neu sifil yn erbyn unrhyw un sydd yn torri hawlfraint a gallai arwain at erlyn neu sifil yn erbyn unrhyw un sydd yn torri hawlfraint a gallai arwain at erlyn neu sifil yn erbyn unrhyw un sydd yn torri hawlfraint.
This map is based upon the Ordnance Survey map by the National Assembly for Wales with the permission of The Controller of Her Majesty's Stationery Office, © Crown copyright. All rights reserved. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.

12 SEP 2008

Appendix B

Photographic Schedule

13-001

13-002

13-003

13-004

13-005

13-006

13-007

13-008

13-009

13-010

13-011

40/41-001

40/41-002

40/41-003

40/41-004

40/41-005

40/41-006

40/41-007

40/41-008

40/41-009

40/41-010

40/41-011

40/41-012

40/41-013

40/41-014

40/41-015

40/41-016

40/41-017

40/41-018

40/41-019

42-001

42-002

42-003

42-004

42-005

42-006

42-007

43-001

43-002

43-003

43-004

43-005

43-006

43-007

43-008

43-009

43-010

44-001

44-002

44-003

44-004

44-005

44-006

44-007

44-008

67-001

67-002

67-003

67-004

67-005

68-001

68-002

68-003

68-004

68-005

68-006

001

002

003

004

005

006

007

008

009

010

011

012

013

014

015

016

017

018

019

020

021

022

12-001

12-002

12-003

12-004

12-005

12-006

12-007

12-008

12-009

12-010

12-011

12-012

12-013

45-001

45-002

45-003

45-004

45-005

45-006

45-007

45-008

45-009

45-010

45-011

45-012

45-013

45-014

45-015

45-016

45-017

45-018

45-019

45-020

45-021

45-022

45-023

45-024

45-025

45-026

45-027

45-028

45-029

45-030

45-031

45-032

45-033

45-034

45-035

45-036

45-037

45-038

45-039

45-040

45-041

45-042

45-043

45-044

45-045

45-046

45-047

45-048

45-049

45-050

45-051

45-052

45-053

45-054

45-055

45-056

45-057

45-058

45-059

45-060

45-061

45-062

45-063

45-064

45-065

45-066

45-067

45-068

45-069

45-070

45-071

45-072

45-073

45-074

45-075

45-076

45-077

45-078

45-079

45-080

45-081

45-082

45-083

45-084

45-085

45-086

45-087

45-088

45-089

45-090

45-091

45-092

45-093

45-094

45-095

45-096

45-097

45-098

45-099

45-100

45-101

45-102

45-103

45-104

45-105

45-106

45-107

45-108

45-109

45-110

45-111

45-112

45-113

45-114

45-115

45-116

45-117

45-118

45-119

45-120

45-121

45-122

45-123

45-124

45-125

45-126

45-127

45-128

45-129

45-130

45-131

45-132

45-133

45-134

45-135

45-136

45-137

50-001

50-002

50-003

50-004

50-005

50-006

50-007

50-008

50-009

50-010

50-011

50-012

50-013

50-014

50-015

50-016

50-017

50-018

50-019

50-020

50-021

50-022

50-023

50-024

50-025

50-026

50-027

50-028

50-029

50-030

50-031

50-032

50-033

50-034

50-035

50-036

50-037

50-038

50-039

50-040

50-041

50-042

50-043

50-044

50-045

50-046

50-047

50-048

50-049

50-050

50-051

50-052

50-053

50-054

58-001

58-002

58-003

58-004

58-005

58-006

58-007

58-008

58-009

58-010

58-011

58-012

58-013

58-014

58-015

58-016

58-017

58-018

58-019

58-020

58-021

58-022

58-023

58-024

58-025

58-026

58-027

58-028

58-029

58-030

58-031

58-032

58-033

58-034

58-035

58-036

58-037

58-038

58-039

58-040

58-041

58-042

58-043

58-044

58-045

58-046

58-047

58-048

58-049

58-050

58-051

58-052

58-053

58-054

58-055

58-056

58-057

58-058

58-059

58-060

58-061

58-062

58-063

58-064

58-065

58-066

58-067

58-068

58-069

58-070

58-071

58-072

58-073

58-074

58-075

59-001

59-002

59-003

59-004

59-005

59-006

59-007

59-008



59-009

59-010

59-011

59-012

59-013

59-014

59-015

59-016

59-017

59-018

59-019

59-020

59-021

59-022

59-023

59-024

59-025

59-026

59-027

59-028

59-029

59-030

59-031

59-032

59-033

59-034

59-035

59-036

59-037

59-038

59-039

59-040

59-041

59-042

59-043

59-044

59-045

59-046

59-047

59-048

59-049

59-050

59-051

59-052

59-053

59-054

59-055

59-056

59-057

59-058

59-059

59-060

59-061

59-062

59-063

59-064

59-065

59-066

59-067

59-068

59-069

59-070

59-071

59-072

59-073

59-074

59-075

59-076


59-077

59-078

59-079

59-080

59-081

59-082

59-083

59-084

59-085

59-086

59-087

59-088

59-089

59-090

59-091

59-092

59-093

59-094

59-095

59-096

59-097

59-098

59-099

59-100

59-101

59-102

59-103

59-104

59-105

59-106

59-107

59-108

59-109

59-110

59-111

59-112

59-113

59-114

59-115

59-116

59-117

59-118

59-119

59-120

59-121

59-122

59-123

59-124

59-125

59-126

59-127

59-128

59-129

59-130

59-131

59-132

59-133

59-134

59-135

59-136

59-137

59-138

59-139

59-140

59-141

59-142

59-143

59-144

59-145

59-146

59-147

59-148

59-149

59-150

59-151

59-152

59-153

59-154

59-155

59-156

59-157

59-158

59-159

59-160

59-161

59-162

59-163

59-164

59-165

59-166

59-167

59-168

59-169

59-170

59-171

65-001

65-002

65-003

65-004

65-005

65-006

65-007

65-008

65-009

65-010

65-011

65-012

65-013

65-014

65-015

65-016

65-017

65-018

65-019

65-020

97-001

97-002

97-003

97-004

97-005

97-006

97-007

97-008

97-009

97-010

97-011

97-012

97-013

97-014

97-015

97-016

97-017

97-018

97-019

97-020

97-021

97-022

97-023

RLP-001

RLP-002

RLP-003

RLP-004

RLP-005

RLP-006

107-001

107-002

107-003

107-004

107-005

107-006

107-007

107-008

107-009

107-010

107-011

107-012

107-013

107-014

107-015

107-016

107-017

107-018

107-019

107-020

107-021


107-022

107-023

107-024

107-025

107-026

107-027

107-028

107-029

107-030

107-031

107-032

107-033

107-034

107-035

107-036

107-037

107-038

109-001

109-002

109-003

109-004

109-005

4109-006

109-007

109-008

109-009

109-010

109-011

109-012

109-013

109-014

109-015

109-016

109-017

109-018

109-019

109-020

109-021

109-022

109-023

109-024

109-025

109-026

109-027

109-028

109-029

109-030

109-031

109-032

109-033

109-034

109-035

109-036

109-037

109-038

109-039

109-040

109-041

109-042

109-043

109-044

109-045

109-046

109-047

109-048

109-049

109-050

109-051

109-052

109-053

109-054

109-055

109-056

109-057

109-058

109-059



109-060

110-001

110-002

110-003

110-004

110-005

110-006

110-007

110-008

110-009

110-010

110-011

110-012

110-013

110-014

110-015

110-016

110-017

110-018

110-019

110-020

110-021

110-022

110-023

110-024

111-001

111-002

111-003

111-004

111-005

111-006

111-007

111-008

111-009

111-010

111-011

111-012

111-013

111-014

111-015

111-016

111-017

111-018

111-019

111-020

111-021

111-022

111-023

111-024

111-025

111-026

111-027

111-028

111-029

111-030

111-031

111-032

111-033

111-034

114-001

114-002

114-003

114-004

115-001

115-002

115-003

115-004

115-005

115-006

115-007

115-008

115-009

115-010

116-001

116-002

116-003

116-004

116-005

116-006

116-007

116-008

116-009

116-010

116-011

116-012

119-001

119-002

119-003

119-004

119-005

119-006

119-007


119-008

119-009

119-010

119-011

119-012

119-013

119-014

119-015

119-016

119-017

119-018

119-019

119-020

119-021

119-022

119-023

119-024

119-025

119-026

119-027

119-028

119-029

119-030

119-031

119-032

119-033

119-034

119-035

119-036

119-037

119-038

119-039

119-040

119-041

119-042

119-043

123-001

123-002

123-003

123-004

123-005

123-006

123-007

123-008

123-009

123-010

123-011

123-012

123-013

123-014

123-015

123-016

123-017

123-018

123-019

123-020

123-021

123-022

123-023

123-024

123-025

123-026

123-027

123-028

123-029

123-030

123-031

123-032

123-033

123-034

124-001

124-002

124-003

124-004

124-005

124-006

124-007

124-008

124-009

124-010

124-011

124-012

124-013

124-014

124-015

124-016

124-017

124-018

124-019

124-020

M-001

M-002

M-003

M-004

M-005

M-006

M-007

128-001

128-002

128-003

128-004

128-005

128-006

128-007

128-008

128-009

128-010

128-011

128-012

128-013

128-014

128-015

128-016

128-017

128-018

128-019

128-020

128-021

128-022

128-023

128-024

128-025

128-026

128-027

128-028

128-029

128-030

128-031

128-032

128-033

128-034

132-001

132-002

132-003

132-004

132-005

132-006

133/143-001

133/143-002

133/143-003

133/143-004

133/143-005

133/143-006

133/143-007

133/143-008

133/143-009

133/143-010

133/143-011

133/143-012

133/143-013

133/143-014

133/143-015

133/143-016

133/143-017

133/143-018

133/143-019

133/143-020

133/143-021

133/143-022

133/143-023

133/143-024

133/143-025

133/143-026

133/143-027

133/143-028

133/143-029

133/143-030

133/143-031

133/143-032

133/143-033

133/143-034

133/143-035

133/143-036

133/143-037

133/143-038

133/143-039

133/143-040

133/143-041

133/143-042

133/143-043

133/143-044

133/143-045

133/143-046

133/143-047

133/143-048

133/143-049

133/143-050

133/143-051

133/143-052

133/143-053

133/143-054

133/143-055

133/143-056

133/143-057

133/143-058

133/143-059

133/143-060

133/143-061

133/143-062

133/143-063

133/143-064

136-001

136-002

136-003

137-001

137-002

137-003

137-004

137-005

137-006

137-007

137-008

137-009

137-010

137-011

137-012

137-013

137-014

137-015

138-001

138-002

138-003

138-004

138-005

138-006

138-007

138-008

139-001

139-002

139-003

139-004

139-005

139-006

146-001

146-002

146-003

146-004

146-005

146-006

146-007

146-008

146-009

146-010

148-001

148-002

148-003

148-004

148-005

149-001

149-002

149-003

149-004

149-005

149-006

149-007

149-008